



Specializing in Commercial Construction

We will hereby provide all Insurance, labor, equipment, material, and supervision required to complete the following scope of work.

**Scope of Work:**

- Labor to include removal of grass and approximately 12" of topsoil across area.
- Area to be scraped measuring 200' deep x 145' wide.
- All spoils to be left on site.
- Once spoils are removed, fill clay will be hauled in and compacted with roller.
- After clay is compacted, fabric will be rolled out and covered with #610 limestone approximately 4" thick.
- #610 limestone will then be covered with approximately 2" of #57 limestone.
- Materials included will be 1500 yds. of clay to bring surface to grade.
- Customer will be responsible for any extra fill clay due to unforeseen circumstances at \$13 per yd.
- Limestone to be provided will be 950 tons of #610 and 500 tons of #57.
- Limestone estimates are approximate and any more or less will be reflected in final invoice.

**\* Pricing good for 90 days due to market volatility\***

This base bid scope of work shall be performed to specifications and in a work like manner for the sum of:

Total Base Bid ----- \$176,250.00

**THE ABOVE TERMS AND PRICE SPECIFICATIONS ARE ASSUMED SATISFACTORY AND HEREBY ACCEPTED.**

Authorized signature \_\_\_\_\_ Dated \_\_\_\_\_

**Quote provided by: Mike Hackley on 03-14-2023**

**LA Contractors License #71691**

**Phone: (337)263-2367 Email: mikejr@hackleyenterprise.com**

*Michael Hackley Jr*  
\_\_\_\_\_  
Signature (Company Representative)

Date: 03-14-23