



TAW POWER SYSTEMS, INC.
509 Time Saver Ave.
Harahan, LA 36582
504-609-3902
Jason.Centola@tawinc.com
Kohler Generator Systems Distributors

TAW Has a New Fleet of Rental Generators

KOHLER POWER SYSTEMS DISTRIBUTOR FOR ALABAMA, SOUTH GEORGIA, FLORIDA, LOUISIANA AND MISSISSIPPI

Date: May 2, 2016
To: St. John the Baptist Sheriff's Office
Attn: Jeff Clement

Offer No: BR1605-0001
Contact: Jason Centola
Contact #: 504-352-8251

Project: ST. JOHN THE BAPTIST SHERIFF OFFICE

(1) One New KOHLER Model **180REOZJG**, EPA Certified **DIESEL** Generator Set, **180 kW**, @ **0.8 PF**, 60 Hz, **3 Phase**, **UL 2200**, **120/208 Volt** with the following:

CONTROLLER:
DEC3000

ENCLOSURE:
Weather
Steel
Critical Silencer; Internal
Tailpipe and Rain Cap

COOLING:
Unit Mounted Radiator
Low Coolant Level Shutdown
Block Heater 120 Volt, 1P, 1800 Watt

FUEL SYSTEM:
Flexible Fuel Lines
Sub-base Fuel Tank, 24 Hour, 400 Gallon
Double Wall with Leak Detector
Fuel Level Gauge
Low Fuel Level Alarm Contact
Local Fill Cap
Vent Package (Normal & Emergency)

GOVERNOR ACCESSORIES:
Electronic Isochronous

GENERATOR ACCESSORIES (Electrical):
Line Circuit Breaker, 3 Pole, 400Amp.
80% Rated, Therm Mag

ENGINE ELECTRICAL ACCESSORIES:
Battery Rack and Cables
Starting Battery, Lead/Acid
Battery Charger: Automatic Float w/Alarms, 24V, 10Amps

CONTROLLER ACCESSORIES LOOSE:
Remote Annunciator Panel

ADDITIONAL ACCESSORIES:

Oil Drain Extension
Lot of Oil and Antifreeze
Corrosion Inhibitor for Radiator
Vibration Isolators - Internal
Air Cleaner Restriction Indicator
One (1) Engine, Generator Parts, Maintenance Manual
One (1) Year Warranty
Initial Start Up and Check Out of System,
Certified Factory Test @ 0.8 P.F.

AUTOMATIC TRANSFER SWITCH:
1 Kohler Automatic Transfer Switch
120/208 Volt, 400 Amp, 3 Phase, 3 Pole,
NEMA 3R Enclosure
Input / Output Module (Qty. 2)
MODEL: **KSS-ACTC-0400S**
One (1) Year Warranty

SUPPLIED BY OTHERS
Off-loading @ Job Site
Installation of System
Supply of Fuel
Infrared and Insulation Testing

TOTAL NET LOT: \$34,838.00

F.O.B. FACTORY, FREIGHT ALLOWED TO JOB SITE.

***Due to changing market conditions delivery/lead times can only be established at the time an order is received at the factory. If the equipment in our OFFER were to be released today the lead time is 11 to 13 weeks. This Estimated lead time is subject to change daily.**

Submittal Lead Time is 2 weeks after receipt of signed offer.

SALES TAX NOT INCLUDED.

Regards,

TAW Power Systems, Inc.

Jason Centola

QUOTATION VALID FOR 30 DAYS FROM THIS OFFER DATE (LISTED ABOVE).

Note: This quote is based on the information supplied by the customer. The quoted price is subject to change if the information supplied by the customer is incomplete or changes at a later date.

Quotation Based Upon:

a) Customer Requested Bill of Material

NOTE: TAW's STANDARD TERMS and CONDITIONS apply to all offers for purchase and any purchase orders accepted by TAW. You may find a copy under the terms and conditions section at TAWINC.com or please contact our office at 800-456-9449 and we will forward you a copy. TAW will transmit a written delivery schedule based on the manufacturer's confirmation, approximately fifteen (15) days after product release. Also included will be the related progress invoice values based on material shipments.

All TAW offers, plans, specifications, and technical drawings are copyrighted works and contain proprietary know-how of TAW, and Buyer has no right to reproduce, distribute or publish copies of TAW's copyrighted works or to create derivative works of TAW's copyrighted works without the express written permission of an authorized representative of TAW.

(OFFER ACCEPTANCE BELOW)

COMPANY

AUTHORIZED SIGNATURE

TITLE

PRINT NAME

DATE

PURCHASE ORDER #

TERMS & CONDITIONS ACKNOWLEDGED:

INITIAL